

# Bidhan Chandra Krishi Viswavidyalaya

WORKS DEPARTMENT, MOHANPUR, NADIA

Tender Notice No C / 02 / 2024 – '25 / 280

Dated : 03.09.2024

## NOTICE INVITING TENDER

Sealed quotations are hereby invited from bonafide tenderers for construction a masonry causeway of the pond bank adjacent to the Central Library under BCKV, Mohanpur, Nadia.

The necessary descriptions are given below

| Sl. No. | Description of Item  | Quantity | Unit  | Rate | Total Amount |
|---------|--|----------|-------|------|--------------|
| (1)     | (3)  | (4)      | (5)   | (6)  | (7)          |
| 1       | Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete.<br>Depth of excavation not exceeding 1,500 mm.   | 9.90     | m3    |      |              |
| 2.      | Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.   | 9.90     | m2    |      |              |
| 3.      | Cement concrete with graded stone ballast (40 mm size excluding shuttering) In ground floor<br>Pakur Variety - 1:3:6 proportion  | 0.75     | m3    |      |              |
| 4.      | Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes.<br>Pakur Variety  | 1.50     | qntl. |      |              |
| 5.      | Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction.<br>For works in foundation and upto roof of ground floor/upto 4 m<br>Other than SAIL/ TATA/RINL   | 1.60     | m3    |      |              |
| 6.      | Brick work with 1st class bricks in cement mortar (1:6)<br>In superstructure, ground floor   | 3.14     | m3    |      |              |
| 7.      | Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over concrete surface]<br>With 1:6 cement mortar - 15 mm thick plaster  | 18.00    | m2    |      |              |
| 8.      | Artificial stone in floor, dado, staircase etc with cement concrete (1:2:4) with stone chips, laid in panels as directed with topping made with ordinary or white cement (as necessary) and marble dust in proportion (1:2) including smooth finishing and rounding off corners including raking out joints or roughening of concrete surface and application of cement slurry before flooring works using cement @ 1.75 kg/sq.m all complete including all materials and labour.<br>In ground floor.<br>3 mm. thick topping (High polishing grinding on this item is not permitted with ordinary cement).<br>Using grey cement - 35 mm. thick | 4.00     | m2    |      |              |

| (1) | (3)  | (4)                             | (5) | (6) | (7) |
|-----|--|---------------------------------|-----|-----|-----|
| 9.  | Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work)<br>With earth obtained from excavation of foundation  | 3.30                            | m3  |     |     |
| 10. | Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor)<br>25 mm to 30 mm shuttering without staging in foundation | 3.80                            | m2  |     |     |
| 11. | Neat cement punning about 1.5mm thick in wall, dado, window sill, floor etc.   | 9.00                            | m2  |     |     |
|     |  | Total Rs.                       |     |     |     |
|     |  | Add GST @ 18% of 'A' Rs.        |     |     |     |
|     |  | Rs.                             |     |     |     |
|     |  | Add Labour cess @ 1% of 'B' Rs. |     |     |     |
|     |  | Gross Total Rs.                 |     |     |     |
|     |  | Say Rs.                         |     |     |     |

Last date & time limit for receipt of sealed quotation at the said office on 10.09.2024 up to 2.00 P.M.

All eligible and willing tenderers are required to submit their quoted rate in company's letter head as per above format along with valid GST Registration, P/Tax Challan, IT Return, PAN Card etc. & drop in tender box kept at Works Department within due date.

The rates quoted in the tender shall remain open for acceptance for 6 (six) months from the date of tender.

The tendering authority does not bind himself to accept the lowest bidder and reserved the right to reject in part or in full or all the tender received or to split up the work in different groups without assigning any reasons thereof.

The tenders which do not fulfil any of the above conditions or are incomplete in any respect liable to summarily rejection.

If the successful tenderer fails to commence the work within 7(seven) days from the date of receipt of work order without showing any valid reason, the work order will be treated as cancelled.

No departmental materials will be issued to the contractor and materials, tools and plants are to be supplied by the contractor.

*Adhikari*  
3.9.24  
In-Charge

Works Department

No. WD / BCKV / CW – 02 / 2024-'25 / 280 / 1 ( 13 ) / 2024 Dated : 03.09.2024

Works Department  
Bidhan Chandra Krishi Vidyapeeth  
Mohanpur- 741252 W.B.

Copy forwarded with a request to display in the notice board for wide circulation to:-

1. The Vice-Chancellor, B.C.K.V, Mohanpur, Nadia.
2. The Registrar (Officiating), B.C.K.V, Mohanpur, Nadia.
3. The Comptroller, B.C.K.V, Mohanpur, Nadia.
4. The Librarian, B.C.K.V, Mohanpur, Nadia with request to upload the tender notice in BCKV Website – www.bckv.edu.in.
5. The Director of Research, B.C.K.V., Kalyani, Nadia.
6. The Director of Farms, B.C.K.V., Mohanpur, Nadia.
7. The Director of Extension Education, B.C.K.V., Mohanpur, Nadia.
8. The Special Officer (Development), B.C.K.V., Kalyani, Nadia.
9. The Dean, Students' Welfare, B.C.K.V., Mohanpur, Nadia.
10. The Dean, Faculty of Agriculture, B.C.K.V., Mohanpur, Nadia.
11. The Dean, Faculty of Horticulture, B.C.K.V., Mohanpur, Nadia.
12. The Dean, Faculty of Agril. Engineering, B.C.K.V, Mohanpur, Nadia.
13. The SAE (Civil), Works Department, B.C.K.V., Mohanpur, Nadia.

*Adhikari*  
3.9.24  
In-Charge  
Works Department  
Bidhan Chandra Krishi Vidyapeeth  
Mohanpur- 741252 W.B.